

City of El Paso - City Plan Commission Staff Report

Case No: SULD-00001 Emerald Heights Development

Application Type: Land Study **CPC Hearing Date:** October 5, 2017

Staff Planner: Armida Martinez, (915) 212-1605, <u>martinezar@elpasotexas.gov</u>

Location: South of Eastlake and West of Peyton

Acreage: 185.48 Rep District: ETJ

Existing Use: Vacant

Existing Zoning: ETJ (Extraterritorial Jurisdiction) **Proposed Zoning:** ETJ (Extraterritorial Jurisdiction)

Nearest Park: Three parks proposed within the land study (8.21 acres

Nearest School: Eastlake High School (across the street)

Park Fees Required: N/A Impact Fee Area: N/A

Property Owner: Northtowne Village Joint Venture

Applicant: Bowling Enterprise, LLC.

Representative: CEA Group

SURROUNDING ZONING AND LAND USE

North: ETJ (Extraterritorial Jurisdiction) / Vacant

South: ETJ (Extraterritorial Jurisdiction) / Elementary School

East: ETJ (Extraterritorial Jurisdiction) / High School

West: ETJ (Extraterritorial Jurisdiction) / Residential Development

PLAN EL PASO DESIGNATION: G4, Suburban Walkable

<u>APPLICATION DESCRIPTION</u>

The applicant proposes a land study for 185.48 acres of land located in the Extraterritorial Jurisdiction. The land study area is predominantly single-family residential with lot sizes ranging from 5,000 to 6000 square feet. Access to the subdivision will be from Peyton and Rojas. The following land uses are proposed:

- 726 single-family residential units within 156.85 acres.
- 1 commercial site within 11.31 acres
- 3 ponding areas within 9.11 acres
- 3 park sites totaling 8.21

The land study does provide a phasing plan and is slated for completion in 2022. This land study is being reviewed under the current subdivision code.

SULD17-00001 1 October 5, 2017

EXCEPTIONS/MODIFICATIONS REQUESTED

The applicant is requesting the following exceptions pursuant to Section 19.10.050 (Roadways participation policies) and Section 19.15.080 (Street Length):

- To allow Rojas Drive to remain as 78' right-of-way with 24' paved lanes, 12' raised median, 4' parkways, and 5' sidewalks
- To allow Emerald Pass to remain as 80' right-of-way with 24' paved lanes, 14' raised median, 4' parkways, and 5' sidewalks

This development is located within the City of El Paso's ETJ. The applicant's proposal to install 4 ft. landscape along Rojas and Emerald Pass will be in character with area as this was a requirement from the County of El Paso.

DEVELOPMENT COORDINATING COMMITTEE

The Development Coordinating Committee recommends approval of Emerald Heights Development Land Study.

Planning Division Recommendation:

Staff recommends approval of the Emerald Heights Development Land Study.

<u>Planning & Inspections Department - Land Development</u>

We have reviewed subject plats and recommend Approval.

The Developer/Engineer shall address the following comments.

- 1. The commercial lot abutting Eastlake Blvd., was originally planned as a residential development and was proposed to discharge into the adjacent pond; need to verify that when the pond is enlarged it will hold the developed run-off for a 100-yr. storm event.
- 2. At the improvement plan stage, protect the subject property from storm-water runoff from the adjacent terrain and vice versa. However, the existing watercourse needs to be conveyed through the subdivision and allowed to continue its path.
- 3. The street reduction variance from 60' to 54' is allowed provided the street carrying capacities are met as per the DDM.
- 4. The land study and subdivision improvement plans must comply with Section 5.2.1 of the DDM. All storm-water runoff from proposed development and its surrounding land areas shall not exceed any of the street carrying capacities. Storm-sewer systems shall be extended to reduce surface flow depths.

Capital Improvement Department - Parks

We have reviewed **Emerald Heights Development Revised Land Study** and on behalf of CID Parks Planning Division we offer Applicant / Engineer the following comments:

Please note that this Land Study is composed of <u>726</u> Residential lots, one **11.31 acre** commercial lot, and includes <u>3 "Park sites"</u> for a total of **8.21 acres** of "Parkland"; per City Standards a **total of 7.26 acres of "Parkland"** and **\$11,310.00** in "Park fees" would have been required however.....

This subdivision is located with-in the City of El Paso Extra Territorial Jurisdiction (ETJ) area but not with-in the areas of potential annexation by the City, therefore meeting the requirements to be excluded from the calculation for "Parkland / fees".

El Paso Water

EPWater does not object to this request.

The proposed Land Study is located within the East El Paso Extraterritorial Jurisdiction (ETJ) within one of the Paseo Del Este Municipal Utility Districts (MUDs) service area. The Paseo Del Este MUD receives wholesale water and wastewater service from the El Paso Water – Public Service Board (EPWater-PSB) in accordance with the Paseo del Este Wholesale Contract and EPWater-PSB Rules and Regulations No. 11.

El Paso County

- 1. The subdivision shall comply with "Appendix 3: Alternative Subdivision Design Standards" of the County Subdivision Regulations.
- 2. The entire ROW for Emerald Pass Avenue should be within the subdivision boundary and fully constructed as was done in the abutting subdivision to the west (Mission Ridge Unit 2). The property abutting the north side is planned to remain open-space and not developed, per the Paseo Del Este Master Plan.
- 3. Emerald Pass Avenue and the other two local streets should be extended through the El Paso Electric Company ROW to provide connectivity to Mission Ridge Unit 2.
- 4. Emerald Pass Avenue should continue the similar cross-section from Mission Ridge Unit Two (four lanes divided minor arterial with a raised landscaped median and 4' parkways). Variance from County Subdivision Regulations will be required for an 80' ROW to accommodate four 12' driving lanes.

Sun Metro

Does not oppose this request.

El Paso Fire Department

Land study is outside city limits. No comments at this time.

Central Appraisal District

No comments received.

El Paso County 911 District


No comments received.


Additional Requirements and General Comments:


- 1. Submit to the Planning & Inspections Department Planning Division the following prior to recording of the subdivision.
 - a. Current certified tax certificate(s)
 - b. Current proof of ownership
 - c. Release of access document, if applicable
 - d. Set of restrictive covenants, if applicable
- 2. Every subdivision shall provide for postal delivery service. The subdivider shall coordinate the installation and construction with the United States Postal Service in determining the type of delivery service for the proposed subdivision. In all cases, the type and location of delivery service shall be subject to the approval of the United States Postal Service.
- 3. Pursuant to Section 19.15.080-Street Length, verify that all proposed block perimeters are less than 2400'.

Attachments

- 1. Location map
- 2. Aerial map
- 3. Land Study
- 4. Exception request
- 5. Application









Castner Center @ Transmountain 4712 Woodrow Bean, Ste. F El Paso, TX 79924 Office: 915.544.5232 Fax: 915.544.5233 web: www.ceagroup.net

September 26, 2017

City of El Paso-Planning and Inspections Department 811 Texas Avenue El Paso, Texas 79901

Attention: Ms. Armida Martinez

Reference: Emerald Heights Land Study - Modification Letter

Dear Ms. Martinez:

On behalf of the Developer for the above referenced development, we are requesting the following exceptions to the subdivision regulations.

Exception No. 1: City Municipal Code 19.15.110-54-foot Roadway

This exception shall consist of a 54-foot roadway cross-sections with (2) 17-foot paved lanes with 6-inch curb and gutter on both sides of the roadway, (2) 5-foot parkways abutting the curb and (2) 5-foot concrete sidewalks.

Exception No. 2: City Municipal Code 19.15.110-78-foot Roadway-Rojas Drive

This exception shall consist of a 78-foot roadway cross-sections with (2) 24-foot paved lanes with 6-inch curb and gutter on both sides of the roadway, (1) 12-foot raised landscape median, (2) 4-foot parkways abutting the curb and (2) 5-foot concrete sidewalks.

Exception No. 3: City Municipal Code 19.15.110-80-foot Roadway-Emerald Pass

This exception shall consist of a 80-foot roadway cross-sections with (2) 24-foot paved lanes with 6-inch curb and gutter on both sides of the roadway, (1) 14-foot raised landscape median, (2) 4-foot parkways abutting the curb and (2) 5-foot concrete sidewalks.

Exception No. 4: City Municipal Code 19.15.080-Block Lengths

This exception shall consist allowing block lengths to exceed the 2,400 linear feet due to topographic constraints.

If you have any questions regarding this issue, please do not hesitate to call me at office number 915.544.5232. We thank you for your cooperation on this issue and look forward to your favorable consideration to our request.

Sincerely, CEA Group

Jorge L. Azcarate, P.E.

Project Manager

I-2000-198.am.cep-modification request 9-26-17 Ac/Ac

engineers • architects • planners





CITY PLAN COMMISSION APPLICATION FOR LAND STUDY APPROVAL

	0.00 XX 0		
Property Land Uses:			
Single-family	ACRES SITES 113.46 734	Office	ACRES SITES
Duplex	<u>113.46</u> <u>734</u>	Street & Alley	43.39 26
Apartment		Ponding & Drainage	9.11 3 .
Mobile Home		Institutional	
P.U.D. Park	8.21 3	Other (specify below)	
School	8,21		
Commercial	11.31 1	Total No. Sites	767
Industrial		Total (Gross) Acreage	185.48
Will the residential s	ites, as proposed, permit developn		
Will the residential s existing residential z What type of utility of	ites, as proposed, permit developn	nent in full compliance with all zo o ound Overhead Cor	ning requirements of the
Will the residential s existing residential z What type of utility of What type of drainag Street sheet flow to basins	ites, as proposed, permit developmone(s)? Yes_X_ No easements are proposed: Undergre te is proposed? (If applicable, list	nent in full compliance with all zo ound Overhead Cor more than one) bund storm sewer systems to disci	ning requirements of the nbination of Both_X,
Will the residential s existing residential z What type of utility What type of drains Street sheet flow to basins Are special public in Is a modification or If answer is "Yes", n	ites, as proposed, permit developmone(s)? Yes_X_Nonesements are proposed: Undergrope to the proposed of the proposed storm inlets and undergroposed storm inlets and undergroposed.	nent in full compliance with all zo ound Overhead Cor more than one) ound storm sewer systems to disci on with development? Yes bdivision Ordinance proposed?	ning requirements of the nbination of Both_X_, arrays to proposed retentionNo
Will the residential sexisting residential zewhat type of utility of what type of drainag Street sheet flow to basins Are special public in Is a modification or If answer is "Yes", p See attached variety.	ites, as proposed, permit developmone(s)? Yes_X_No. casements are proposed: Undergrous proposed? (If applicable, list proposed storm inlets and undergroup provements proposed in connection case explain the nature of the Sullease explain the nature of the moters.	nent in full compliance with all ze o o o o o o o o o o o o o o o o o o	ning requirements of the nbination of Both_X_, arrays to proposed retentionNo

11.	Chillet Clitatora	ntowne Village Join	t Venture 4712 Wood	row Bean, Ste. A El Paso Texas (Zip)	79924 (915) 757-1827 (Phone)
12.	Developer Bowling Ent	erprises, LLC. 4	712 Woodrow Bean, S		(915) 757-1827
	(Na	me & Address)		(Zip)	(Phone)
13.	Engineer CEA Group	4712 Woodrow B	lean, Ste. F	El Paso Texas 79924	(915) 544-5232
		me & Address)		(Zip)	(Phone)
	*Effective September 1, 2014, a 3% technology fee has been added to all Planning application fees.		OWNER SIGNA	ATURE:	Ki

NOTE: SUBMITTAL OF AN APPLICATION DOES NOT CONSTITUTE ACCEPTANCE FOR PROCESSING UNTIL THE PLANNING DEPARTMENT REVIEWS THE APPLICATION FOR ACCURACY AND COMPLETENESS.



City Development Department 811 Texas | P.O. Box 1890 | El Paso, Texas 79950-1890| (915) 212-0085